



**MODEL 4100 TITAN PM / WM ROTARY ARM (OVERHEAD)
SEMI-AUTOMATIC STRETCH WRAP SYSTEM
GENERAL SPECIFICATIONS**

Note: PM / WM refers to the machine mounting style. Requires a secure structural wall, or a building column or post for mounting. The footprint is smaller than free-standing styles, requiring less floor space. (Note – dimensional details of the existing column or post must be submitted when ordering the PM version so that the appropriate post-mount bracket can be provided.)

PRODUCTION SPEED

- 1-30 loads per hour

NOTE: Process rates will vary with load size, number of wraps & forklift load/unload time

LOAD CAPACITY

- Maximum load weight: Unlimited (floor supported)
 - Maximum load size: 50" W x 50" L (71" max. load diagonal) x 86" H (plus up to 4" top overlap)
-

ROTARY ARM

- Double flange bearing support system
 - Twin V-belt drive pulleys with belt tensioner
 - 1-12 RPM rotational speed c/w soft start acceleration
 - Final revolution deceleration and positive stop alignment
 - 1/2 HP DC variable speed motor
-

**FILM CARRIAGE
ELEVATOR**

- 1/2 HP DC variable speed motor
 - Direct flat belt drive system
 - Maintenance free 12 point carriage guidance system
-

**FILM DELIVERY
SYSTEM**

- **NEW Super Rapid Thread II**™ 20" capacity pre-stretch film carriage
 - *Special Film Threading Device – Uniquely orientates the sticky side of the film against the pre-stretch rollers and the inside of the load.*
 - 1/2 HP DC variable speed motor
 - Fully electronic dynamic dancer corner compensation
 - 33 to 313% fixed stretch capability
-

FILM DELIVERY SYSTEM
...continued...

- Pre-stretch ratio variable by easy sprocket change
- **Rapid Thread™ Safety Door with auto power cut-off switch**
- Superior **film-to-roller** contact area
- Lifetime warranty on pre-stretch rollers

CONTROL FEATURES

- Simple to operate
- **PANASONIC** PLC
- Power Off – On – Reset switch & Power On indicator light
- Single button Auto Wrap Cycle Start/Pause
- Cycle Pause for applying top sheets
- Base or Top Wraps First program
- Reinforce Wrap control for mid-wrapping
- Up Only or Up/Down wrap program
- Emergency Stop button
- Rotary Arm Jog switch
- Film Carriage Lower/Raise switch
- Film tension (Force-to-Load) control
- Separate film carriage raise & lower speed controls
- Variable rotary arm speed control
- Rotary arm and carriage elevator dynamic braking system
- Triple beam type auto load height sensing photo-eye, detects dark or shiny loads
- Separate 1 to 9 revolution top & bottom wrap control
- NEMA 12 control panel enclosure
- Dust tight slip ring assembly
- Non-proprietary UL/CSA approved components

STRUCTURAL FEATURES

- All structural steel construction
- Integral structural steel wall/floor mounting stand
- Electro-static powder coated paint finish

SAFETY FEATURES

- **Rotary Arm Obstruction Emergency Safety Stop Sensor**

ELECTRICAL INPUT REQUIREMENT

- 115 Volts 1 Phase 60 Hz 15 Amps